



**REVISIONS:**



DRAWN BY: DAS

[REDACTED]

PANDA PROJECT #: S8-21-D8043

ARCH PROJECT #: P7356.2

\_\_\_\_\_

\_\_\_\_\_

TRUE WARM & WELCOME 2300 R1



FOOTING SCHEDULE		
MARK	DIMENSIONS	REINFORCING
F26.12	2'-6" X 12" CONT.	(3) #5 CONT. & #5 @ 12" O.C. TRANSV.

 - DESIGNATES SHEARWALL TYPE

**NOTES:**

1. USE 10d COMMON NAILS.
2. NAIL PANEL FACES @ 12" O.C.
3. USE 1/2" PLYWOOD.
4. STAGGER PLYWOOD JOINT AND SILL PLATE NAILING.
5. FRAMING MEMBERS OR BLOCKING SHALL BE PROVIDED AT THE EDGES OF ALL SHEETS IN SHEARWALLS.
6. REFER TO 915-200 FOR HOLD DOWN ANCHOR EMBEDMENT.
7. HOLD DOWN ANCHORS MUST BE TIED IN PLACE PRIOR TO FOUNDATION INSPECTION.
8. FRAMING AT ADJOINING PANEL EDGES SHALL BE 3 INCH NOMINAL OR THICKER AND NAILS SHALL BE STAGGERED WHERE NAILS ARE SPACED AT 3" O.C. OR ARE ON EACH FACE.

FOUNDATION NOTES	1
Scale: NO SCALE	S-100

FOUNDATION PLAN	A
Scale: 1/4"=1'-0"	S-100